BRUHAT BANGALORE MAHANAGARA PALIKE

BILL OF QUANTITIES (BOQ)

Name of work: Providing and Fixing Sign boards in Hegadenagara Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Issued to Technical Manager , KRIDL	
				In Figures	In Words
1	**30.62**	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	86.92	Rupees Eighty Six and Ninety Two Paise Only
2	**7.65**	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete	cum	5159.02	Rupees Five Thousand One Hundred Fifty Nine and Two Paise Only
3	**22.96**	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 withOPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete	cum	5598.92	Rupees Five Thousand Five Hundred Ninety Eight and Ninety Two Paise Only
4	**252.00**	Providing MS Pipe Name Board Made 3" (75mm) Dia M.S Pipe for verticalpole and 3 Nos of Horizontal Support pipe of 11/2" (38") dia pipe each of Length 1m signage board of size 60X45 cm and 60X23 cm size made of 16 guage M.S Sheet welded to M.S Square tube frame of size 25X25 mm all manual are cut size and all items electricals welded as per the drawing all joints are grinded smooth and painted with 2 cots of approved colour synthetic enamel paint over a coat of industrical prime and painting the required detail in fountain on either side of board as per the details provided etc complete.	No.	6506.00	Rupees Six Thousand Five Hundred Six Only
5	**45360.00**	KSRRBM800-10 Painting New letter and Figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade complete as per specification. ("II) English and Roman Hyphen and the line not tobe measured and Piad for	No.	0.45	and Forty Five Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the Bangalore Mahanagara Palike and as directed.
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Executive Engineer (Byatarayanapura)
Bruhath Bangalore Mahanagara Palike

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore-92

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

CONTRACTOR

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010